

District of Columbia Water and Sewer Authority David L. Gadis, General Manager



Creek Bed Sewer Repair and Rehabilitation Project

### **Soapstone Valley Park**

February 2022

Presentation

**DCWATER.COM** 

### **Our Discussion**



### **PROJECT NEED AND BENEFITS**

# **Soapstone Valley Park Project**



- Soapstone stream restoration and trail rehabilitation
- 6,200 linear feet of sewer pipe rehabilitation
- Repair of two impaired stormwater outfalls

# Why Now?

- Protect human health and the environment
  - Deterioration of the sewer pipes causing sewage leaks (seven recorded sewer leaks/ overflows since 2014, on average once/year)
  - Exposed pipes vulnerable to severe damage from falling trees, stones, and ongoing and potentially accelerating erosion
  - Increasing likelihood of major break that spills sewage into the creek and park
- Alternative is continued emergency repairs
  - Have a much bigger footprint
  - Less opportunity for a thoughtful approach
  - Will not deliver full community benefits



### **Benefits to the Community**

- Eliminates risk of major sewage spills into park
- Ensures long-term, safe recreational use of a valued community asset
- Formalizes Park trail and replaces invasive species with native species
- Stabilizes creek channel to reduce erosion and reconnects to natural floodplain
- Reduces unwanted odors from sewers and manholes



Upper Watts Branch located in Rockville, MD.

# **National Park Service**

- Floodwaters threaten sewers and Soapstone Valley Park.
- NPS and DC Water have worked for 10 years on planning this project.
- The selected alternative is the least impactful.
- Permits are required for all work.
- All disturbed areas of the park will be restored.

For Questions and Concerns About the Park Please Contact: Nick Bartolomeo Resources, Lands and Planning Manager 202-579-8494 | <u>nick\_bartolomeo@nps.gov</u>



### We Hear You



Limits of Disturbance (LOD) Stormwater Outfalls 8

# **No-VOC\*, Styrene-Free Resin**

- For this project, DC Water will use a resin that contains no volatile organic compounds (VOCs)\* and no styrene.
- This will increase the cost of the project but minimize the risk of emissions.
- DOEE is currently assessing the need for additional measures for use of no-VOC, styrene free resin and hot water cure.
- DC Water will continue to work with DOEE to verify any additional mitigation measures to use standard resin (with steam curing) in DC.



### **Hot Water Curing Method**

| Pro  | Con                           |
|--|-------------------------------|
| There are no intentional emissions with hot water curing                             | Longer construction duration  |
| <ul> <li>Can be completed within approved Limits of<br/>Disturbance (LOD)</li> </ul> | Additional equipment required |

# **Minimizing Tree Impacts**

- Number of trees affected has always been – and continues to be a driving factor in the design of this project.
- Authorized to cut no more than 371 trees.
- Most of the tree impact is to protect exposed manholes and sewers and stream restoration.
- Second most is for work to repair the two stormwater outfalls.
- Tree-cutting <u>must be complete by</u> <u>March 31</u> to avoid impacts to federally protected bats.
- Native trees and vegetation will be replanted as part of mitigation



### **Construction Approach Addresses Community Concerns**

- Third-party air quality monitoring during CIPP work with data made available to the public
  - Air quality monitoring during the CIPP portion of construction will be conducted by an independent third party.
  - Details of air quality monitoring plan are under development and will include consultation with DOEE.
- Protection of Blue Plains Advanced WWTP confirmed
- Lining work will be completed beginning from the downstream end (near Broad Branch Road) and moving upstream

### **Near-Term Construction Schedule Update**

- September 2021:
  - DC Water Issued Notice to Proceed to contractor for Soapstone project
- February 2022:
  - Site visits to stake out LOD and tag trees for removal, trimming, or protection
  - Signage installed, park is closed to visitors
  - Tree removals begin
- March 2022:
  - Tree removals continue
  - Initial detailed construction schedule complete\*
- Spring 2022:
  - Access path construction
  - Stormwater outfall construction begins
- Summer 2022:
  - Sewer lining work begins in the Park

Schedule driver: Need to complete tree cutting by March 31

\* Tentative timeline, dependent on contractor

### **DC Water's Role During Construction**

- DC Water retains inspection responsibility for construction from start through site restoration and clean up including adherence to work plan and specifications as well as quality control
- Contractor's safety plan is reviewed by DC Water's Safety Department who also oversee implementation

### SOAPSTONE PROJECT PLANNING AND ALTERNATIVES ANALYSIS

## **Decision Making Process**



Park impacts, constructability, and construction duration identified as driving criteria, establishes initial LOD.

Environmental review and permitting process is complex and lengthy for projects on NPS property, establishes permitted LOD. DCW standard practice is "open bid" to foster competitive bidding.





### **2010 Sewer System Condition Assessment**

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

- Full evaluation of sewers and manholes within the Park
- CCTV inspection reveals sewer pipe deficiencies and leaks
- Exposed sewer pipes and manholes at risk of damage and failure
- Sanitary manhole inspects show deterioration and water infiltration
- Stormwater outfalls need repair to comply with District municipal separate storm sewer system (MS4) Permit
- Progression of deterioration since 2010 assessment



**Extensive Water Infiltration** 



At-risk Sewer Pipe Crossing Stream



Manhole Exposed by Erosive Stream Channel

### 2010 Sewer System and Stormwater Outfall Condition Assessment Recommendations

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

- Protect exposed sewers and manholes within and adjacent to the creek to the extent practicable
- Repair 2 stormwater outfalls per MS4 permit
- Repair, Replace or Rehabilitate
  - ~6,200 feet of sanitary pipe
  - ~22 Sanitary manholes



### **Stormwater Outfall Repair**

Alternatives Analysis 2011-2013 Environmental Review and Permitting

- Repair stormwater outfall to comply with MS4 Permit
- Second largest driver of LOD to access outfall



### Protecting Exposed Manholes and Sewers and Restore the Creek

Alternatives Analysis 2011-2013 Environm

**Environmental Review and Permitting** 

- Protect exposed sewers and manholes within and adjacent to the creek to the extent practicable
- Largest driver for LOD for access



# **Sewer Repair Alternatives Analysis**

| Alternatives Analysis 2011-2013 Environmental Review and Permitting |  | al Review and Permitting Procurement   |
|---|--|--|
|   | Alternative  | Reason For Elimination or Advancement  |
| ✓   | CIPP Trenchless  | <ul> <li>Compatible with existing site conditions</li> <li>Repairs the sewers</li> <li>Little additional impact to the park beyond<br/>stormwater and sewer and manhole protection work</li> </ul> |
| X   | Trenchless Pipe Relocation along<br>Audubon Terrace NW or Albemarle<br>St NW | <ul> <li>Requires pump stations (Albemarle St)</li> <li>Requires extensive geotechnical borings (Audubon Terrance)</li> <li>Requires aerial sewer pipe crossing, sewer remains at risk</li> </ul>  |
| X   | Open Cut Pipe Replacement (Same Location and New Location in Park)           | <ul> <li>Large footprint (including open cut within the creek)</li> <li>Significant ground disturbance</li> <li>Construction infeasible in certain locations</li> </ul>                            |
| X   | Trenchless Construction in Same<br>Alignment                                 | <ul> <li>Infeasible from engineering standpoint (shallow depth of sewer,<br/>pipe crossings would require excavation)</li> </ul>   |

# Sewer Repair Alternatives Analysis (continued)

| Alternati | ves Analysis 2011-2013 Environmental   | Review and Permitting Procurement   |
|-----------|--|---|
|           | Alternative  | Reason For Elimination or Advancement   |
| X         | Trenchless Construction in New<br>Alignment  | <ul> <li>Requires aerial sewer pipe crossing, sewer remains at risk</li> <li>Dependent on extensive soil investigations</li> <li>Incompatible with varying soil profiles<br/>anticipated to be in the park</li> </ul>   |
| X         | Installation of a Siphon   | <ul> <li>Difficult to maintain, subject to frequent blockages</li> <li>Design criteria for sewer flow rates and velocities incompatible with Soapstone sewers</li> </ul>  |
| X         | Other Trenchless Rehabilitation<br>Methods (i.e., Spiral Wound Pipe,<br>Fold-and-form, Horizontal<br>Directional Drilling (HDD), Pipe<br>Bursting, Pipe Ramming) | <ul> <li>Does not provide structural rehabilitation (Spiral Wound Pipe)</li> <li>Incompatible with sewer pipe size in Soapstone (Fold-and-Form)</li> <li>Not appropriate for gravity-fed sewers (HDD)</li> <li>Incompatible with exposed sewers (Pipe Bursting)</li> <li>Difficult to maneuver in varying soil conditions (Pipe Ramming)</li> </ul> |
| X         | Reroute Alternative  | <ul> <li>Open cut installation of new sewer pipes</li> <li>Large footprint and ground disturbance</li> <li>Requires pump stations and permanent vehicular access</li> <li>Only removes partial flow; remaining sewers would require rehabilitation</li> </ul>   |

# **Overview of Cured-in-Place Pipe (CIPP)**

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

Procurement

- CIPP is a type of trenchless technology that involves insertion of a **tube liner** containing resin inside the existing pipe.
- Following insertion, the tube liner is cured in place becoming a structural entity.
- Three curing installation methods: water cure, steam cure, Ultraviolet (UV) cure
- CIPP Factors:
  - Liner Material
    - Determines shape and thickness of resin
    - Can vary according to curing method
  - Liner Resin
    - VOCs are function of the resin
  - Curing
    - Emissions are function of curing method and resin
    - Different equipment and access requirements



Animation Courtesy of IPR Solutions





Figure Courtesy of US Trenchless

# **Steam Cure Installation Method**

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

- Liner pulled or inverted using pressurized air
- Cured with steam under pressure
- Temporary release of steam only during curing
- Cure time 1-2 hours
- Can line 800 feet 1000 feet at one time, can line up to 45degree bend
- DC Water requires 15-foot barrier around manholes and 8-foot stack for vented steam to minimize worker exposure



# Water Cure Installation Method

#### Alternatives Analysis 2011-2013

#### **Environmental Review and Permitting**

- Liner inverted using water
- Cured with hot water
- Cure time 4-8 hours depending on temperature and other conditions
- Controlled release of water to sanitary sewer and onto WWTP
- Can line 1,000 feet 2,000 feet at one time, can line up to 45-degree bend
- Requires temporary structures to create water column for liner installation







# **Ultraviolet (UV) Installation Method**

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

- First US install in 2007; more frequent use in last 4-5 years
- Fiberglass liner that is pulled via a winch from downstream manhole
- Air is used to invert the liner, CCTV to inspect the liner, UV light to cure the liner
- Process requires no water for curing, but still needed for cleaning
- Limited on installation lengths and bends in pipes
- No steam plume, but odor could still be detected





# **Overview: Final Approved LOD**



- Protection of exposed sewers/manholes and stream restoration is the largest factor for LOD and number of impacted trees
- Stormwater outfall repair is the second largest driver for LOD extents and number of impacted trees
- CIPP work can be done within the established LOD
- LOD does not include access to all manholes

### Why Hot Water Curing Method for Soapstone?

| Pro              |   | Con                           |
|------------------|---|-------------------------------|
| • There wate     | e are no intentional emissions with hot<br>r curing | Longer construction duration  |
| • Can k<br>Distu | e completed within approved Limits of rbance (LOD)  | Additional equipment required |

### ENVIRONMENTAL REVIEW AND PERMITTING

# **NEPA Overview**

#### **Alternatives Analysis**

**Environmental Review and Permitting 2014-2018** 

National Environmental Policy Act (NEPA) requires federal agencies to assess environmental effects of major federal actions (funding, federal property, others)

- Each federal agency establishes guidelines for NEPA implementation
- National Parks Service (NPS) was Lead Agency for preparation of the Soapstone Environmental Assessment (EA)
- The purpose of an EA is to provide a concise public document to help officials make informed decisions accounting for the environmental consequences



#### **Overview of NEPA Process**

### **Soapstone Environmental Review Timeline**



### **Soapstone Environmental Assessment**

#### **Alternatives Analysis**

#### **Environmental Review and Permitting 2014-2018**

- EA prepared in accordance with:
  - 40 CFR 1500-1508 federal regulations governing NEPA compliance
  - NPS Director's Order 12 (Conservation Planning, Environmental Impact Analysis, and Decision-Making)
  - NPS NEPA Handbook
- The EA evaluated two alternatives:
  - No Action Alternative
  - CIPP Trenchless Alternative
    - Did not specify the CIPP cure method
    - No CIPP technology was excluded
    - Questions received on technology during public review confirmed all technologies would be allowed during bid phase
  - Other alternatives evaluated and dismissed (EA Appendix D)

- EA evaluated proposed project compliance with applicable local and federal regulations and per NPS direction
  - NPS Management Policies 2006
  - NPS Director's Order 12 Conservation Planning, Environmental Impact Analysis, and Decision-Making
  - NPS Director's Order 14 *Resource Damage Assessment* and *Restoration*
  - NPS Director's Order 77-1 Wetland Protection
     (Statement of Findings)
  - NPS Director's Order 77-2 Floodplain Management (Statement of Findings)
  - Executive Order 11990 Protection of Wetlands
  - Section 106 of the National Historic Preservation Act
  - Section 7 of the Endangered Species Act
  - Clean Water Act (Section 303(d)
  - 401, 404, 501)
  - DC Regulations

### **Environmental Assessment Establishes** Limits of Disturbance

Alternatives Analysis 2011-2013

**Environmental Review and Permitting** 

- Iterative design process with NPS sets approved LOD
- Smallest LOD within which project can be feasibly constructed
- Any variation to LOD risks reopening NEPA process





### **Soapstone Permitting Review and Approval Timeline**



# **Soapstone Construction Phase Permits**

|  | Agency  | Department                                 | Permit / Approval   |
|--|---|--|---|
|  | National Park Service (NPS)   | Rock Creek Park Division                   | <ul><li>Special Use Permits (SUP)</li><li>Right of Way Permit</li></ul>   |
| <b>FEMA</b>                                    | Federal Emergency<br>Management Agency<br>(FEMA)                    | National Flood Insurance<br>Program        | Letter of Map Revision  |
| * * * DEPARTMENT<br>OF ENERGY &<br>ENVIRONMENT | District Department of<br>Energy & Environment<br>(DOEE)            | Watershed Protection<br>Division           | Letter of Map Revision  |
|  |   | Fisheries and Wildlife<br>Division         | <ul> <li>Time of Year Restriction Waiver for In-Water<br/>Work (as needed)</li> </ul>   |
| d.<br>¢dcra                                    | District Department of<br>Transportation (DDOT)                     | Public Space Regulation<br>Division (PSRD) | <ul> <li>Occupancy Permit</li> <li>Public Inconvenience Permit</li> <li>Construction and Excavation Permit Steel Plate<br/>Permit (TBD)</li> <li>Oversize / Commercial Vehicle Permit</li> <li>Loading Permit (TBD)</li> <li>Manhole Access Permit (TBD)</li> </ul> |
|  |   | Urban Forestry<br>Administration           | <ul><li>Public Space Tree Permit</li><li>Special Tree Removal (TBD)</li></ul>   |
|  | District Department of<br>Consumer and Regulatory<br>Affairs (DCRA) | Permit Center                              | <ul><li>After Hours Permit (TBD)</li><li>Excavation Permit</li></ul>  |
|  | DC Water  | Compliance Program                         | Fire Hydrant Use Permit   |

### PROCUREMENT

## Procurement

**Alternatives Analysis** 

**Environmental Review and Permitting** 

Procurement 2020 - 2021

- DC Water specification for CIPP work is nationally recognized among utility peers for being comprehensive and innovative.
- In addition to technology, the specification covers experience with similar work, and the proposal has to include the safety record of the bidders as part of the evaluation.
- Bid documents structured to incentivize contractor to minimize tree removal
- DC Water lays out constraints and allows the contractor to select a suitable technology within the contractual constraints
- Prior to start of CIPP work, contractor is required to develop and have a site safety plan approved by DC Water.
- In addition, DC Water will have an independent contractor conduct air quality monitoring.
- Air quality monitoring data obtained during Soapstone project will inform future CIPP work specifications.

# **Decision Making Process**

**23 Public Engagement** Activities Since 2013



### SOAPSTONE PROJECT WHERE ARE WE NOW

### Where We Are

No-VOC, styrene-free resin

Water curing process

Third party air quality monitoring

No additional trees

Fits within approved Limits of Disturbance in the EA

The need to complete this project is urgent

Tree removal must be complete before March 31 due to federally protected bats

### Thank you

- This has been a lengthy, complex process
- Community participation and patience are vital contributions to protecting public health and the environment

#### Before



After

Upper Watts Branch located in Rockville, MD.

